BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

MODIFIED APPROVED TENDER SCHEDULE –'B'

Name of Work:-: Construction RCC drain at Sai baba Temple in Kondappa layout ward No:02 of Yelahanka sub division

Sl	Description	Unit	Approved Qty	Approved Rate Technical Manager (West) KRIDL, BBMP.	
				Rate	Rate in Words
1	KSRB 2-2.1 : earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications, specification, No, KBS 2.1(a) / 2.3.5, No. 5/ Item No. 2.3/ PWD SR 2015-16	Cum	116.22	192.24	Rupees one hundred ninety two and paise twenty four only
2	KSRB 100-1 Loading and unloading ofstone aggregates / sand/ kanker/ Moorum /soil KSRRB M100-1 Placing tipper at loading with front end loader dumpting turning for return trip excluding time for haulged and return trip complete as per specification item No 17.1 page 130 and KSRB M.100.4.1 costof haulage excluding loading and unloading MORTH to a distance of 4.00 K.M (Item No 17.4 Page 130 (SR 2015-16)	Cum	116.22	85.00	Rupees eighty five only
3	KSRRB M300-53 : Construction of embankment with approved material Gravel/Murrum with all lifts and leads, trasnporting to site, spreading, grading to required slope and compacting to meet requirement Table 300-2 complete as per specifications (which includes cost of gravel / murrum, watering charges & compaction by vibratory roller) MORTH Specification No. 305. (Page No. 144 & Item No. 19.60)	Cum	66.00	311.04	Rupoees three hundred eleven and paise four only
4	KSRB-4-1.7 : Providing and laying in position plain cement concrete of mix 1:3:6 withOPC cement at 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.465cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2, No. 12/ Item No. 4.2/ PWD SR 2015-16	Cum	41.37	5236.92	Rupees five thousand two hundred thirty six and paie ninety two only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Sl. No.	Description	Unit	Approved Qty	Approved Rate Technical Manager (West) KRIDL, BBMP.	
				Rate	Rate in Words
5	KSRB 4.2.2 : Providing and laying in position plain cement concrete of mix M20 withOPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @0.460cum with superplastesisre @ 3lts conforming to IS9103-1999Reffirmed machine mixed exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls(any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour HOM of machinery, curing, complete as per specifications. Specification. No. KBS 4.1,4.6, No. KBS 4.1,4.2, No. 13/ Item No. 4.11/ PWD SR 2015-16	Cum	19.53	6198.12	Rupees six thousand one hundr ninety eight and paise twelve or
6	KSRB 4.9.2:providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 Page No. 17/ Item No. 4.46/ PWD SR 2014-15	Qit.	11.72	6980.58	Rupees six thousand nine hundre eighty and paise fifty eight only
7	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, attached pilasters, bittresses,buttresses plinth and string course including cost of all materials, labour complete as per specifications. Specification NO KBS 4.6.2 Page No. 15/ Item No. 4.31/ PWD SR 2015-16	Sqm	148.80	306.72	Rupees three hundred six and pais seventy two only
8	Providing precast Covering Slab for Drain (10cm thick)	Sqm	55.80	1498.00	
9	KSRRB M600-6: cement concrete pavement, construction unreinforced plain cement concrete pavement, thickness as per design, over a prepared sub base with 43 grade cement or any other type as per clause 1051.2.2 with 25mm and down size graded granite metal coarse aggregates and fine aggregtes with surperlatisiser @ 3its confirjming to IS103-1999 fine ,reaffirmed-2008 mixed in a concrete mixed of not eless than 0.6 cum capacity and appropriate weigh batcher as per approved mix design capacitylaid in approved fixed side form wedges stee plates including levellingthe from work as per deawing) & spreading the concrot and finished racer compacted using needle , screed and plate vibrator and finished in a continous operation including provision orf contraction , ex[pansion construction and longitudinal joints including groove cutting charges joint filler separation memberane selant primer joint sealant admixtures ad approved curing compound finishing to lines and grades as per drwng complete as per specifin M 30 at 360 kg per cim coarse aggregate @ 0.69cum and fine aggregate @0.49cum	Cum	22.00	5957.28	Rupees five thousand nine hundr fifty seven and paise twenty eig only

Signature of the Contractor

EXECUTIVE ENGINEER KRIDL, BBMP DIVISION BENGALURU-560 010

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.